



Town of Mendon
2282 U.S. Route 4
Mendon, Vermont 05701
802-775-1662
www.mendonvt.org

September 5, 2017

REQUEST FOR BIDS
Town of Mendon, VT
Ditch Repair and Culvert Installation

The Town of Mendon is accepting proposals for TH#1 Meadowlake Drive Erosion Control Project. The project length is approximately 1,300 located on Meadowlake Drive from Bridge 3 extending beyond Sherwood Drive another 250 feet to a culvert.

The Contractor must have workman's compensation and insurance.

Beginning at Bridge 3 on the east side of the road:

- Clean out stone lined ditch approx. 50' and reestablish ditch
- Clean out outlet end of culvert and catch basin
- Above culvert #01-02 cut back bank from the roadway 3' wide by 100' in length
- Above culvert #01-02 establish "U" shaped ditch and stone line approx. 200' in length
- Above driveway #2 establish "U" shaped ditch and stone line approx. 100' in length
- Above culvert #01-04 establish "U" shape ditch and stone line approx. 285' in length to Sherwood Drive
- Replace driveway #1 culvert: pull out existing and replace with 15" X 20' plastic culvert, set and backfill with 1.5" gravel. Place stone headers for inlet and outlet. (Mendon will supply the culvert)
- Approx. 15' above driveway #1 culvert cut back bank from the roadway 3' wide by 100' in length
- On the northeastern side of Sherwood Drive cut back bank from the roadway 3' wide by 100' in length
- On the northeastern side of Sherwood Drive establish "U" shaped ditch and stone line approx. 250' in length to the culvert.
- On the southeastern side of Meadowlake Drive across from Sherwood Drive taper ground 3-4' from the edge of road to allow for water runoff approx. 100' (there is a stone wall located within this section, do not disturb the wall but clean road edge to the wall)
- Any sloped bank that the disturbed area that is not stone lined must have hay mats laid down at the completion of the work day in accordance with Better Roads Best Practices.
- The Town Road Crew will provide signage and flagging.
- Construction timeline is expected to be completed within 5 working days Mon.-Fri. unless otherwise arranged with the town.
- Construction must be complete by October 25, 2017.

A mandatory site visit will be held on September 13th at 9:00 AM. Please meet at the Mendon Town Office at 2282 US Route 4, Mendon, VT. Bids are due at the Town Office on September 20, 2017 at 9:00 AM. Please refer questions to Sara Tully, Mendon Town Administrator at 802-775-1662 or mendonadmin@comcast.net.

REQUEST FOR BIDS
Town of Mendon, VT
Ditch Repair and Culvert Installation

The Town of Mendon is requesting bids from qualified contractors to establish ditches and install a 15" X 20' culvert. A detailed Request for Bids can be found posted www.mendonvt.org. A mandatory site visit to be held at the Mendon Town Office, 2282 US Route 4, Mendon, VT 05701 on September 13, 2017 at 9:00 AM. Bids shall be delivered to the Mendon Town Office no later than September 20, 2017 at 9:00 AM. Proposals submitted later than this date and time will not be opened, and will be rejected.